$\frac{\text{OOR LOADS:}}{\text{OOR LOADS:}} \qquad \frac{2 \times 3}{3}$		CONCENTRATED	
OCCUPANCY OR USE:	LIVE LOAD:	LOAD:	
FLOORS (UNLESS NOTED OTHERWISE)	150 p.s.f.	400 lbs.	
VEHICLE BAY FLOOR - HS20-44 TRUCK	640 p.s.f.	18 kips(FOR	MOMENT
		26 kips(FOR	SHEAR)

SNOW LOADS:

ROOF DESIGN SNOW LOAD, Pf (NON-REDUCIBLE) 30 p.s.f. EXPOSURE FACTOR, C. 1.0 IMPORTANCE FACTOR, I THERMAL FACTOR, Ct GROUND SNOW LOAD, Pa 30 p.s.f.

SEISMIC LOADS:

IMPORTANCE FACTOR, IE 1.25 MAPPED SPECTRAL RESPONSE ACCELERATIONS: 0.059 SITE CLASS . SPECTRAL RESPONSE COEFFICIENTS: ... 0.197

..... 0.094 SEISMIC DESIGN CATEGORY

BASIC SEISMIC-FORCE-RESISTING SYSTEMS: ORDINARY STEEL MOMENT FRAME DESIGN BASE SHEAR: BY PRE ENGINEERED METAL BUILDING MANUFACTURER RESPONSE MODIFICATION FACTOR, R:EQUIVALENT LATERAL FORCE PROCEDURE ANALYSIS PROCEDURE:

WIND LOADS:

BASIC WIND SPEED (3-SECOND GUST): 100 m.p.h. WIND EXPOSURE C IMPORTANCE FACTOR, Iw 1.15 INTERNAL PRESSURE COEFFICIENT, GC pi 0.18±

FLOOD LOADS:

NOT IN FLOOD HAZARD ZONE

- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE THE LOCATION OF MECHANICAL OPENINGS, FLOOR DRAINS, INSERTS, DEPRESSIONS, BURIED CABLES AND UTILITIES, ETC. WITH ARCHITECTURAL, CIVIL, MECHANICAL AND ELECTRICAL DRAWINGS.
- 3. VERIFY ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS, NOTIFY ENGINEER OF DISCREPANCIES. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS.

SOILS AND FOUNDATIONS

- 1. FOUNDATION DESIGN IS IN ACCORDANCE WITH THE SOIL REPORT BY HEPWORTH-PAWLAK GEOTECHNICAL, INC, NUMBER 308121B, DATED MARCH 4, 2009, AND THE UPDATED LETTER DATED NOVEMBER 22, 2010. (2)
- DESIGN OF DRILLED PIERS IS BASED ON THE FOLLOWING CRITERIA: MAXIMUM ALLOWABLE END BEARING PRESSURE 30,000 p.s.f. MINIMUM ALLOWABLE END BEARING PRESSURE 15,000 p.s.f. MINIMUM PENETRATION INTO BEDROCK 8.0 feet

THE MAXIMUM VARIATION OF THE CENTER OF ANY DRILLED PIER AT ITS TOP FROM THE REQUIRED LOCATION SHALL NOT BE MORE THAN 5-1/2% OF ITS DIAMETER AND NO PIER SHALL BE OUT OF PLUMB MORE THAN 1% OF ITS LENGTH.

3. SOIL BENEATH SLABS ON GRADE SHALL BE NATIVE, SOLID UNDISTURBED MATERIAL FREE OF WATER, FROST OR FOREIGN DEBRIS, OR STRUCTURAL FILL COMPACTED IN ACCORDANCE WITH THE SOILS REPORT AND SPECIFICATIONS WITH MINIMUM DENSITY AS FOLLOWS:

SLABS-ON-GRADE: 95% OF STANDARD PROCTOR, ASTM D698.

4. A REPRESENTATIVE OF THE SOILS ENGINEER SHALL INSPECT THE OPEN EXCAVATION TO DETERMINE THAT THE SOIL TYPE AND CONDITIONS ARE CONSISTENT WITH DESIGN CRITERIA OF THE SOILS REPORT. IF THE SOIL PROPERTIES ARE FOUND TO BE DIFFERENT FROM THIS CRITERIA, THEN THE ENGINEER SHALL BE PROMPTLY NOTIFIED SO THAT THE FOUNDATION DESIGN MAY BE REVIEWED.

CONCRETE:

ALL CONCRETE DESIGN, MATERIALS AND CONSTRUCTION SHALL CONFORM TO ACI STANDARD 318-08, THE INTERNATIONAL BUILDING CODE, 2009 EDITION, THE CRSI MANUAL OF STANDARD PRACTICE (CURRENT EDITION) AND THE PROJECT SPECIFICATIONS.

MATERIAL SPECIFICATIONS: ASTM A615, GR. 60 REINFORCING BARS ... WELDED WIRE FABRIC ASTM A185 REINFORCING BARS (WELDED) ASTM A706, GR. 60

3. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH IN 28 DAYS AS FOLLOWS:

A. GENERAL STRUCTURAL CONCRETE: GRADE BEAMS & WALLS 4500 p.s.i. CEMENT TYPE I/II FLOOR SLABS ... 4500 p.s.i. CEMENT TYPE I/II SLABS-ON-GRADE 4500 p.s.i. CEMENT TYPE I/II (WITH 1.5 lbs OF FIBERMESH PER CUBIC YARD) EQUIPMENT PEDESTALS 4500 p.s.i. CEMENT TYPE I/II DRILLED PIERS (5"-7" SLUMP) 3750 p.s.i. CEMENT TYPE I/II

REINFORCEMENT SHALL BE DETAILED IN ACCORDANCE WITH THE ACI DETAILING MANUAL, LATEST EDITION. FORMWORK SHALL BE DESIGNED, ERECTED AND REMOVED IN ACCORDANCE WITH THE

REINFORCEMENT SHALL BE PLACED SO THAT THE FOLLOWING MINIMUM CONCRETE PROTECTION IS

PROVIDED, UNLESS NOTED OTHERWISE. CONCRETE SURFACES POURED AGAINST GROUND 3" CLEAR FORMED SURFACES EXPOSED TO GROUND OR WEATHER: BARS #6 AND LARGER 2" CLEAR BARS #5 AND SMALLER..... 1-1/2" CLEAR

SLABS-ON-GRADE AT CENTERS

REINFORCEMENT SHALL BE SECURELY TIED AND SHALL BE SUPPORTED WITH METAL CHAIRS OR HUNG FROM FORMS.

CONTINUOUS HORIZONTAL BARS AND CORNER BARS IN GRADE BEAMS AND SLABS SHALL BE LAPPED AS FOLLOWS AT SPLICES. SPLICE LOCATIONS SHALL BE STAGGERED WHERE POSSIBLE.

> No. 6 BARS No. 7 BARS <u>& LARGER</u> STRENGTH & SMALLER 38 dь 48 d^D 4500 p.s.i (WHERE $d_b = BAR DIAMETERS$)

SPLICES IN GRADE BEAM REINFORCING, IF REQUIRED, SHALL BE AS FOLLOWS: BOTTOM BARS AT DRILLED PIERS .. MID SPAN BETWEEN DRILLED PIERS

ADDITIONAL (2) #6 BARS (ONE EACH FACE) WITH A 3'-0" PROJECTION SHALL BE PLACED DIAGONALLY

ACROSS THE CORNERS OF ALL OPENINGS AND VERTICAL STEPS IN WALLS.

GRADE BEAMS BELOW GRADE SHALL HAVE BACKFILL PLACED EQUALLY ON BOTH SIDES UNTIL THE REQUIRED LEVELS ARE REACHED.

CONSTRUCTION JOINTS IN SLABS ON GRADE SHALL BE SPACED AT INTERVALS ENCLOSING NO MORE THAN 144 SQUARE FEET WITH A MAXIMUM OF 12 FEET IN ANY ONE DIRECTION UNLESS OTHERWISE NOTED ON DRAWINGS. CONSTRUCTION JOINTS SHALL BE FORMED WITH METAL LOAD KEY JOINT SUPPLIED BY JAHN CONCRETE PRODUCTS OR APPROVED EQUAL. FOR CONSTRUCTION JOINTS IN SLABS 6" AND THICKER PROVIDE 1 INCH DIAMETER X 24" LONG SMOOTH DOWELS AT 18" ON CENTER OILED ONE END. REFER TO PROJECT MANUAL FOR

CONSTRUCTION JOINTS (COLD JOINTS) SHALL BE PROVIDED IN GRADE BEAMS, WHICH ARE OVER 70 FEET IN A STRAIGHT RUN. KEYWAYS SHALL BE PROVIDED AT ALL CONSTRUCTION JOINTS IN

GRADE BEAMS. 12. CONTROL JOINTS IN SLABS MAY BE TOOLED OR SAWCUT AS INDICATED ON THE DRAWINGS

ALL JOINTS SHALL BE APPROVED BY THE ENGINEER.

SEALING OF CONSTRUCTION JOINTS.

STRUCTURAL STEEL:

ALL STRUCTURAL STEEL DESIGN, MATERIALS, FABRICATION AND ERECTION SHALL CONFORM TO THE AISC SPECIFICATION, 13TH EDITION, THE INTERNATIONAL BUILDING CODE, 2009 EDITION AND THE PROJECT SPECIFICATIONS.

> XREF FILENAME: G BASE DWG: G:\
> PLOT STYLE FILE: 1050C.ett FILENAME: \G:\LFMSDD\20166\Informational Drawings\I19\I19.dwg

REVISIONS				
0\(\)	DATE	DESCRIPTION		
1	07/28/2011	ISSUED FOR FOUNDATION PERMIT SUBMITTAL TO PPRBD (EQUIP, MAINT. AND STO. BLDG)		
2	08/24/2011	ISSUED FOR CONSTRUCTION PER PPRBD FDTN PERMIT #H93002 (EQUIP., MAINT. AND STO. BLDG)		
3	11/23/2011	ISSUED FOR BUILDING PERMIT SUBMITTAL TO PPRBD (EQUIP. MAINT. & STOR. BLDG.)		
4	01/09/2012	ISSUED FOR CONSTRUCTION PER PPRBD BUILDING PERMIT #H93002 (EQUIP. MAINT. & STO. BLDG.)		
	_			

THIS DRAWING IS THE PROPERTY OF GMS, INC., AND IS NOT TO BE RE-PRODUCED, MODIFIED OR USED FOR ANY OTHER PROJECT OR EXTENSION OF THIS PROJECT EXCEPT BY AGREEMENT WITH THIS COMPANY.

2011 GMS, INC.

STRUCTURAL GENERAL NOTES EQUIPMENT MAINTENANCE AND STORAGE BUILDING HAROLD D. THOMPSON REGIONAL WATER RECLAMATION FACILITY LOWER FOUNTAIN METROPOLITAN SEWAGE DISPOSAL DISTRICT

LOWER	FUUNTAIN	METROPOLITAN SEWAGE DISPOSAL			
RAWN	SKC				
SIGNED	MG	GMS, INC.			
HECKED	RJS				
NTE	2011	CONSULTING ENGINEERS 611 N. WEBER, SUITE 300 COLORADO SPRINGS, COLORADO 80903			
ROJECT NO	20166.410				
IS FILE NO.	2599				

