

**GMS, INC.**  
CONSULTING ENGINEERS  
611 NORTH WEBER, SUITE 300  
COLORADO SPRINGS, COLORADO 80903-1074

TELEPHONE (719) 475-2935  
TELEFAX (719) 475-2938

EDWARD D. MEYER, P.E.  
ROGER J. SAMS, P.E.  
GREGORY R. WORDEN, P.E.  
THOMAS A. McCLERNAN, P.E.

KEN L. WHITE, P.L.S.  
DAVID R. FRISCH, P.L.S.  
MARK A. MORTON, P.E.  
JASON D. MEYER, P.E.

**ENGINEER'S SUPPLEMENTAL INSTRUCTION NO. TWO (002)**  
**(Via Posting to FTP Site and Electronic Mail)**

TO: Wes Weaver  
John Jacob  
Jeff Burst  
**Weaver General Construction Co.**

DATE: November 16, 2010

FROM: Roger J. Sams, P.E.  
David R. Frisch, P.L.S.  
**GMS, Inc.**

RE: Harold D. Thompson Regional Water Reclamation Facility (HDTRWRF)-Phase 1  
**ENGINEER'S SUPPLEMENTAL INSTRUCTION NO. TWO (ESI-002)**

This ESI-002 is being posted on the project FTP site as of this date in regard to the depth of pavement section in Lower Fountain Heights. The project Specification Section 02500-Paving and Surfacing, Paragraph 3.2.B.2., as issued on May 20, 2010, states:

- B. Thickness of Pavement Section
  - 2. Place in lifts with a maximum compacted thickness of 3 inches
    - a. Place two lifts to a minimum total thickness of 5 inches prior to commencement of major site work

Based on discussion at Design Team Conference No. 31 on November 12, 2010 and previous telephone conversations, Specification Section 02500, Paragraph 3.2.B.2. shall be modified to read as follows:

- B. *Thickness of Pavement Section*
  - 2. *Place in lifts with a maximum compacted thickness of 2½ inches*
    - a. *Place two lifts to a minimum total thickness of 4½ inches prior to commencement of major site work*

cc: Lower Fountain Metropolitan Sewage Disposal District via Electronic Mail  
Fountain Sanitation District via Electronic Mail  
Colorado Centre Metropolitan District via Electronic Mail